City of Fairfield, Ohio
Bid Opening - Results

Project(s): Resor Road Improvements
Project Estimate: $765,000
Date: May 31, 2011 (City of Fairfield, Council Chambers)

Contractor (Address & Phone)	Base Bid	Addendums 1 & 2 Received	Bid Security	Non-Collusion Affidavit	PP Taxes Affidavit
Mt. Pleasant Blacktopping Co., Inc. 3199 Production Drive Fairfield, OH 45014 513-874-3777	$1,036,296.97	No	Yes - Bond	Yes	Yes
Welsh Excavation Co., Inc. 5780 State Route 128 Cleves, OH 45002 513-353-9014	$857,783.45	Yes – 1 & 2	Yes - Bond	Yes	Yes
W.G. Stang LLc 2403 Jacksonburg Road Hamilton, OH 45011 513-863-6924	$1,122,511.00	Yes – 1 & 2	Yes - Bond	Yes	Yes
Ford Development Corp. 11148 Woodward Lane Cincinnati, OH 45241 513-772-1521	$1,127,719.00	Yes – 1 only	Yes - Bond	Yes	Yes
Prus Construction Co. 5325 Wooster Road Cincinnati, OH 45226 513-321-7774	$1,018,828.90	Yes –2	Yes - Bond	Yes	Yes

** These bids will be reviewed by the Public Works Department and a recommendation will be made to Council. There is no guarantee that the contract will be awarded to the lowest bidder. Contracts are awarded to the bidder deemed to be the best and the lowest bid.

City of Fairfield, Ohio
Bid Opening - Results

Project(s): Resor Road Improvements
Project Estimate: $765,000
Date: May 31, 2011 (City of Fairfield, Council Chambers)

Contractor (Address & Phone)	Base Bid	Addendums 1 & 2 Received	Bid Security	Non-Collusion Affidavit	PP Taxes Affidavit
Rack & Ballauer Excavatiing Co., Inc. 11321 Paddy's Run Rd. Hamilton, OH 45013 513-738-7000	$1,052,031.37	Yes – 1 & 2	Yes - Bond	Yes	No
Sunesis Construction Co. 2610 Crescentville Rd. West Chester, OH 45069 513-326-6000	$1,276,224.94	Yes – 1 & 2	Yes - Bond	Yes	Yes
REI Construction 4845 Augspurger Road Hamilton, OH 45011 513-868-9087	$1,043,998.35	Yes	Yes - Bond	Yes	Yes

** These bids will be reviewed by the Public Works Department and a recommendation will be made to Council. There is no guarantee that the contract will be awarded to the lowest bidder. Contracts are awarded to the bidder deemed to be the best and the lowest bid.

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID $ 1,036,296 97

CONSIDERATION FOR MATERIAL $ 621,778 18

CONSIDERATION FOR LABOR $ 414,518 79

TOTAL LABOR AND MATERIAL $ 1,036,296 97

TOTAL AMOUNT WRITTEN IN WORDS One Million Thirty Six Thousand Two Hundred Ninety Six Dollars 97/100

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

By: _____ Signature

Benjamin P. Davis Name

President Title

Mt. Pleasant Blacktopping Co. Inc. Company

3199 Production Drive Address

Fairfield Ohio 45014 City/State/Zip

513-874-3777 Telephone

31-0654767 S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
X Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No.___ _ Yes _ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	20,000	20,000
202	Fence Removed	FEET	20	1.25	25
202	Walk Removed	SQ YD	245	5	1,225
202	Pipe Removed, 24" and Under	FEET	462	2	924
202	Catch Basin Removed	EACH	3	350	1050
202	Pavement Removed - Driveways	SQ YD	476	6	2856
202	Special - Stone Retaining Wall Removed	EACH	3	500	1500
203	Excavation Not Including Embankment	CU YD	3573	15	53595
203	Embankment	CU YD	495	5	2475
204	Proof Rolling	HOURS	3	5	15
204	Embankment	CU YD	200	5	1000
204	Subgrade Compaction	SQ YD	4025	2	8050
204	Subgrade Compaction (Driveways)	SQ YD	305	4	1,220
204	Excavation of Subgrade	CU YD	300	15	3000
204	Granular Material	CU YD	100	33	3300
204	Geotextile Fabric	SQ YD	100	6	600
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	5	500
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	6	600
207	Erosion Control	LUMP	1	2500	2500
207	Tempoary Filter Fabric Fence	FEET	1300	3	3900
207	Dandy Bags	EACH	8	115	920
207	Beaver Dams	EACH	8	115	920
606	Guardrail Type 5	FEET	75	32.50	2437.50
606	Guardrail Anchor Type A	EACH	1	2300	2300
606	Guardrail Anchor Type E-98 Assembly	EACH	1	2300	2300
608	Concrete Walk	SQ FT	245	5	1225
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	650	1300
609	Curb, Type 6	FEET	1020	16	16,320
659	Water	MGAL	4	1.10	4.40
659	Commercial Fertilizer	TON	2	550	1,100
660	Sodding	SQ YD	2332	6	13,992
690	Mailbox Support System, Single	EACH	33	300	9900
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	650	650

DRAINAGE					
Item No.	Description	Units	Est. Qty		

601	Rock Channel Type C with Filter Fabric	CU YD	54	85.-	4590.-
602	Concrete Masonry	CU YD	4	500.-	2000.-
603	6" Conduit, Type E	FEET	100	4.-	400.-
603	6" Conduit, Type F	FEET	100	4.-	400.-
603	12" Conduit, Type C	FEET	347	45.-	15,615.-
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	55.-	10,285.-
603	12" Conduit, Type D	FEET	525	45.-	23,625.-
603	24" Conduit, Type D	FEET	49	69.-	3,185.-
603	24" Conduit, Type C	FEET	24	65.-	1560.-
604	Catch Basin, No. 2-2B	EACH	7	950.-	6650.-
604	Catch Basin, No. 2-3	EACH	2	1200.-	2400.-
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	450.-	1350.-
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	12.-	15,240.-
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	850.-	5100.-
604	Sanitary Manhole Reconstructed to Grade	EACH	2	2000.-	4000.-
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	52.-	66,612.-
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	77.-	4389.-
304	Aggregate Base	TON	1418	17.25	24,460.50
304	Aggregate Base (Driveways)	TON	46	34.50	1587.-
254	Pavement Planing	SQ YD	5035	3.-	15,105.-
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	68.-	58,548.-
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	93.-	2,790.-
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	74.-	54,390.-
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	99.-	2574.-
407	Tack Coat For Intermediate Course	GAL	400	2.25	900.-
408	Prime Coat	GAL	1600	0.25	400.-
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	48.-	40,704.-
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4.25	30,493.75

N

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	30,000	30,000
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1200	25200
638	Fire Hydrant Removed	EACH	4	850	3400
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	4500	22,500
638	6" Water Main Connection to Ex Main	EACH	1	3800	3,800
638	10" Water Main Connection to Ex Main	EACH	2	3800	7600
638	6" Cut-in-Valve	EACH	1	3800	3800
638	8" Valve	EACH	1	800	800
638	10" Valve	EACH	3	1200	3600
638	8" x 6" Reducer	EACH	2	0 01	0 02
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	16,000	16,000
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	98	2450
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	105	4200
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	123	285360
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	23	2553
630	Sign Flat Sheet	SQ FT	62	16	992
630	Ground Mounted Support No. 3 Post	EACH	8	128	1024
630	Removal of Ground Mounted Sign and Disposal	EACH	5	10	50
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	10	50
630	Removal of Ground Mounted Sign and Reerection	EACH	1	175	175
642	Center Line	MILE	0.57	1450	826 50

N

642	Edge Line	MILE	1	1100	1100
642	Dotted Line, 4"	LF	88	1.10	96.80
642	Channelizing Line	LF	166	1.25	207.50
642	Lane Arrow	EACH	3	85	255
642	Word on Pavement	EACH	1	200	200
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	14,000	14,000
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	24	22,800
623	Construction Layout Staking	SUM	LUMP	12,000	12,000
624	Mobilization	SUM	LUMP		
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	200	200
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	26	24,700
	TOTAL BASE BID				$1,036,296.92

N

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID	#857,783.45
CONSIDERATION FOR MATERIAL	400,512.90
CONSIDERATION FOR LABOR	457,270.55
TOTAL LABOR AND MATERIAL	857,783.45

TOTAL AMOUNT WRITTEN IN WORDS EIGHT HUNDRED FIFTY-SEVEN THOUSAND SEVEN HUNDRED EIGHTY-THREE & 45/100 DOLLARS.

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

Jeffrey A. VanFossen — Signature

JEFFREY A. VANFOSSEN — Name

V.P. — Title

WELSH EXCAVATION CO., INC. — Company

5780 SR 128 — Address

CLEVES, OHIO 45002 — City/State/Zip

(513) 353-9014 — Telephone

31-1182125 — S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
X Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No. 1, 2 X Yes ___ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

Resor Road

BID FORM

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	24,000 -	24000 -
202	Fence Removed	FEET	20	5-	100 -
202	Walk Removed	SQ YD	245	9-	2205-
202	Pipe Removed, 24" and Under	FEET	462	2-	924-
202	Catch Basin Removed	EACH	3	250-	750 -
202	Pavement Removed - Driveways	SQ YD	476	9-	4284-
202	Special - Stone Retaining Wall Removed	EACH	3	50-	150 -
203	Excavation Not Including Embankment	CU YD	3573	12 -	42,876-
203	Embankment	CU YD	495	4-	1980-
204	Proof Rolling	HOURS	3	90 -	270 -
204	Embankment	CU YD	200	4 -	800 -
204	Subgrade Compaction	SQ YD	4025	0.75	3018.75
204	Subgrade Compaction (Driveways)	SQ YD	305	0.75	228.75
204	Excavation of Subgrade	CU YD	300	12-	3600-
204	Granular Material	CU YD	100	33.25	3325-
204	Geotextile Fabric	SQ YD	100	2.15	215-
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	6.05	605 -
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	5.80	580-
207	Erosion Control	LUMP	1	3000 -	3000 -
207	Tempoary Filter Fabric Fence	FEET	1300	2.25	2925-
207	Dandy Bags	EACH	8	70 -	560 -
207	Beaver Dams	EACH	8	90-	720-
606	Guardrail Type 5	FEET	75	19.50	1462.50
606	Guardrail Anchor Type A	EACH	1	162.75	162.75
606	Guardrail Anchor Type E-98 Assembly	EACH	1	105 -	105 -
608	Concrete Walk	SQ FT	245	1090.25	1090.25
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	340 -	680 -
609	Curb, Type 6	FEET	1020	12.40	12,648-
659	Water	MGAL	4	150 -	600-
659	Commercial Fertilizer	TON	2	525-	1050-
660	Sodding	SQ YD	2332	3-	6996 -
690	Mailbox Support System, Single	EACH	33	100 -	3300 -
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	250 -	250 -

DRAINAGE					
Item No.	Description	Units	Est. Qty		

N

Resor Road BID FORM

601	Rock Channel Type C with Filter Fabric	CU YD	54	90-	4860-
602	Concrete Masonry	CU YD	4	325-	1300-
603	6" Conduit, Type E	FEET	100	13.50	1350-
603	6" Conduit, Type F	FEET	100	13.50	1350-
603	12" Conduit, Type C	FEET	347	21.75	7547.25
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	32.50	6077.50
603	12" Conduit, Type D	FEET	525	19.60	10,290-
603	24" Conduit, Type D	FEET	49	45.25	2217.25
603	24" Conduit, Type C	FEET	24	52.25	1254-
604	Catch Basin, No. 2-2B	EACH	7	900-	6300-
604	Catch Basin, No. 2-3	EACH	2	1400-	2800-
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	225-	675-
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	8-	10,160-
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	275-	1650-
604	Sanitary Manhole Reconstructed to Grade	EACH	2	2000-	4000-
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	54.50	69,814.50
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	81-	4617-
304	Aggregate Base	TON	1418	19-	26,942-
304	Aggregate Base (Driveways)	TON	46	19-	874-
254	Pavement Planing	SQ YD	5035	2.65	13,342.75
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	73.50	63,283.50
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	97.65	2929.50
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	79.80	58,653-
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	104-	2704-
407	Tack Coat For Intermediate Course	GAL	400	2.35	940-
408	Prime Coat	GAL	1600	2.35	3760-
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	40.70	34,513.60
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4.15	29,776.25

N

Resor Road

BID FORM

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	12,500 -	12,500 -
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1240 -	26,040 -
638	Fire Hydrant Removed	EACH	4	250 -	1000 -
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	3850 -	19,250 -
638	6" Water Main Connection to Ex Main	EACH	1	1200 -	1200 -
638	10" Water Main Connection to Ex Main	EACH	2	1200 -	2400 -
638	6" Cut-in-Valve	EACH	1	2275 -	2275 -
638	8" Valve	EACH	1	1070 -	1070 -
638	10" Valve	EACH	3	1600 -	4800 -
638	8" x 6" Reducer	EACH	2	175 -	350 -
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	11,708 -	11,708 -
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	128.25	3206.25
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	104.85	4194 -
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	92 -	213,440 -
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	22 -	2442 -
630	Sign Flat Sheet	SQ FT	62	14.75	914.50
630	Ground Mounted Support No. 3 Post	EACH	8	122.75	982 -
630	Removal of Ground Mounted Sign and Disposal	EACH	5	15.75	78.75
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	15.75	78.75
630	Removal of Ground Mounted Sign and Reerection	EACH	1	42 -	42 -
642	Center Line	MILE	0.57	1360 -	775.20

N

Resor Road

BID FORM

642	Edge Line	MILE	1	1035-	1035-
642	Dotted Line, 4"	LF	88	1.05	92.40
642	Channelizing Line	LF	166	1.25	207.50
642	Lane Arrow	EACH	3	80-	240-
642	Word on Pavement	EACH	1	105-	105-
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	9705-	9705-
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	26.50	25,175-
623	Construction Layout Staking	SUM	LUMP	11,325-	11,325-
624	Mobilization	SUM	LUMP	1500-	1500-
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	150	150-
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	26.50	25,175-
	TOTAL BASE BID			$ 857,783.45	

N

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID	1,122,511.00
CONSIDERATION FOR MATERIAL	600,000.00
CONSIDERATION FOR LABOR	522,511.00
TOTAL LABOR AND MATERIAL	1,122,511.00
TOTAL AMOUNT WRITTEN IN WORDS	One Million One Hundred Twenty Two Thousand Five Hundred Eleven Dollars

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

Ricky Redelman	Signature
RICKY REDELMAN	Name
MEMBER	Title
W.G. STANG LLC	Company
2403 JACKSONBURG ROAD	Address
HAMILTON OHIO 45011	City/State/Zip
513-863-6924	Telephone
16-1629947	S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
✓ Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No. 1 2 ✓ Yes ___ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

Resor Road

BID FORM

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	50000 00	50000 00
202	Fence Removed	FEET	20	1 00	20 00
202	Walk Removed	SQ YD	245	1 00	245 00
202	Pipe Removed, 24" and Under	FEET	462	10 00	4620 00
202	Catch Basin Removed	EACH	3	75 00	225 00
202	Pavement Removed - Driveways	SQ YD	476	20 00	9520 00
202	Special - Stone Retaining Wall Removed	EACH	3	100 00	300 00
203	Excavation Not Including Embankment	CU YD	3573	20 00	71460 00
203	Embankment	CU YD	495	20 00	9900 00
204	Proof Rolling	HOURS	3	60 00	180 00
204	Embankment	CU YD	200	15 00	3000 00
204	Subgrade Compaction	SQ YD	4025	2 00	8050 00
204	Subgrade Compaction (Driveways)	SQ YD	305	10 00	3050 00
204	Excavation of Subgrade	CU YD	300	15 00	4500 00
204	Granular Material	CU YD	100	30 00	3000 00
204	Geotextile Fabric	SQ YD	100	2 00	200 00
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	6 00	600 00
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	6 00	600 00
207	Erosion Control	LUMP	1	4000 00	4000 00
207	Tempoary Filter Fabric Fence	FEET	1300	1 00	1300 00
207	Dandy Bags	EACH	8	50 00	400 00
207	Beaver Dams	EACH	8	75 00	600 00
606	Guardrail Type 5	FEET	75	30 00	2250 00
606	Guardrail Anchor Type A	EACH	1	1000 00	1000 00
606	Guardrail Anchor Type E-98 Assembly	EACH	1	2250 00	2250 00
608	Concrete Walk	SQ FT	245	10 00	2450 00
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	300 00	600 00
609	Curb, Type 6	FEET	1020	12 50	12750 00
659	Water	MGAL	4	100 00	400 00
659	Commercial Fertilizer	TON	2	250 00	500 00
660	Sodding	SQ YD	2332	7 50	17490 00
690	Mailbox Support System, Single	EACH	33	100 00	3300 00
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	250 00	250 00

DRAINAGE					
Item No.	Description	Units	Est. Qty		

N

Resor Road

BID FORM

601	Rock Channel Type C with Filter Fabric	CU YD	54	90	4860
602	Concrete Masonry	CU YD	4	300	1200
603	6" Conduit, Type E	FEET	100	8	800
603	6" Conduit, Type F	FEET	100	8	800
603	12" Conduit, Type C	FEET	347	30	10410
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	35	6545
603	12" Conduit, Type D	FEET	525	30	15750
603	24" Conduit, Type D	FEET	49	50	2450
603	24" Conduit, Type C	FEET	24	75	1800
604	Catch Basin, No. 2-2B	EACH	7	1000	7000
604	Catch Basin, No. 2-3	EACH	2	1500	3000
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	250	750
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	8	10160
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	250	1500
604	Sanitary Manhole Reconstructed to Grade	EACH	2	1000	2000
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	50	64050
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	120	6840
304	Aggregate Base	TON	1418	40	56720
304	Aggregate Base (Driveways)	TON	46	75	3450
254	Pavement Planing	SQ YD	5035	2	10070
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	55	47355
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	160	4800
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	72	52920
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	160	4160
407	Tack Coat For Intermediate Course	GAL	400	2	800
408	Prime Coat	GAL	1600	4	6400
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	50	42400
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4	28700

N

Resor Road

BID FORM

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	50000 00	50000 00
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1500 00	31500 00
638	Fire Hydrant Removed	EACH	4	350 00	1400 00
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	4000 00	20000 00
638	6" Water Main Connection to Ex Main	EACH	1	1000 00	1000 00
638	10" Water Main Connection to Ex Main	EACH	2	1250 00	2500 00
638	6" Cut-in-Valve	EACH	1	1500 00	1500 00
638	8" Valve	EACH	1	1250 00	1250 00
638	10" Valve	EACH	3	2000 00	6000 00
638	8" x 6" Reducer	EACH	2	150 00	300 00
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	12500 00	12500 00
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	100 00	2500 00
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	110 00	4400 00
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	120 00	278400 00
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	24 00	2664 00
630	Sign Flat Sheet	SQ FT	62	20 00	1240 00
630	Ground Mounted Support No. 3 Post	EACH	8	150 00	1200 00
630	Removal of Ground Mounted Sign and Disposal	EACH	5	35 00	175 00
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	35 00	175 00
630	Removal of Ground Mounted Sign and Reerection	EACH	1	150 00	150 00
642	Center Line	MILE	0.57	1500 00	855 00

N

642	Edge Line	MILE	1	1000 00	1000 00
642	Dotted Line, 4"	LF	88	1 00	88 00
642	Channelizing Line	LF	166	1 50	249 00
642	Lane Arrow	EACH	3	75 00	225 00
642	Word on Pavement	EACH	1	90 00	90 00
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	15000 00	15000 00
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	22 00	20900 00
623	Construction Layout Staking	SUM	LUMP	15000 00	15000 00
624	Mobilization	SUM	LUMP	10000 00	10000 00
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	750 00	750 00
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	24 00	22800 00
	TOTAL BASE BID				1,122,511 00

Resor Road Improvements

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID $1,127,719

CONSIDERATION FOR MATERIAL $500,000

CONSIDERATION FOR LABOR $627,719

TOTAL LABOR AND MATERIAL $1,127,719

TOTAL AMOUNT WRITTEN IN WORDS ONE MILLION ONE HUNDRED TWENTY SEVEN THOUSAND SEVEN HUNDRED NINETEEN DOLLARS

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

THE FORD DEVELOPMENT CORP. OHIO SEAL CORPORATE

	Signature
ROBERT F. HENDERSON	Name
PRESIDENT	Title
FORD DEVELOPMENT CORP.	Company
11148 WOODWARD LANE	Address
CINCINNATI, OHIO 45241	City/State/Zip
513-772-1521	Telephone
31-0802784	S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
✓ Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No. 1 ✓ Yes ___ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

Resor Road

BID FORM

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	50000	50000
202	Fence Removed	FEET	20	5	100
202	Walk Removed	SQ YD	245	2	490
202	Pipe Removed, 24" and Under	FEET	462	3	1386
202	Catch Basin Removed	EACH	3	200	600
202	Pavement Removed - Driveways	SQ YD	476	9	4284
202	Special - Stone Retaining Wall Removed	EACH	3	1000	3000
203	Excavation Not Including Embankment	CU YD	3573	15	53595
203	Embankment	CU YD	495	10	4950
204	Proof Rolling	HOURS	3	70	210
204	Embankment	CU YD	200	5	1000
204	Subgrade Compaction	SQ YD	4025	1.50	6037.50
204	Subgrade Compaction (Driveways)	SQ YD	305	1.50	457.50
204	Excavation of Subgrade	CU YD	300	10	3000
204	Granular Material	CU YD	100	30	3000
204	Geotextile Fabric	SQ YD	100	1	100
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	4	400
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	4	400
207	Erosion Control	LUMP	1	2000	2000
207	Tempoary Filter Fabric Fence	FEET	1300	.50	650
207	Dandy Bags	EACH	8	100	800
207	Beaver Dams	EACH	8	100	800
606	Guardrail Type 5	FEET	75	18	1350
606	Guardrail Anchor Type A	EACH	1	1000	1000
606	Guardrail Anchor Type E-98 Assembly	EACH	1	1800	1800
608	Concrete Walk	SQ FT	245	4	980
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	300	600
609	Curb, Type 6	FEET	1020	17	17340
659	Water	MGAL	4	1	4
659	Commercial Fertilizer	TON	2	1	2
660	Sodding	SQ YD	2332	6	13992
690	Mailbox Support System, Single	EACH	33	120	3960
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	1000	1000

DRAINAGE					
Item No.	Description	Units	Est. Qty		

N

Resor Road

BID FORM

601	Rock Channel Type C with Filter Fabric	CU YD	54	80	4320
602	Concrete Masonry	CU YD	4	100	400
603	6" Conduit, Type E	FEET	100	8	800
603	6" Conduit, Type F	FEET	100	12	1200
603	12" Conduit, Type C	FEET	347	46	15962
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	61	11407
603	12" Conduit, Type D	FEET	525	48	25200
603	24" Conduit, Type D	FEET	49	70	3430
603	24" Conduit, Type C	FEET	24	75	1800
604	Catch Basin, No. 2-2B	EACH	7	1000	7000
604	Catch Basin, No. 2-3	EACH	2	2000	4000
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	300	900
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	7	8890
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	300	1800
604	Sanitary Manhole Reconstructed to Grade	EACH	2	500	1000
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	50	64050
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	100	5700
304	Aggregate Base	TON	1418	25	35450
304	Aggregate Base (Driveways)	TON	46	25	1150
254	Pavement Planing	SQ YD	5035	1.50	7552.50
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	52	44772
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	147	4410
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	72	52920
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	120	3120
407	Tack Coat For Intermediate Course	GAL	400	2	800
408	Prime Coat	GAL	1600	4.25	6800
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	40	33920
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4	28700

N

Resor Road

BID FORM

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	85000	85000
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1200	25200
638	Fire Hydrant Removed	EACH	4	300	1200
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	4000	20000
638	6" Water Main Connection to Ex Main	EACH	1	1500	1500
638	10" Water Main Connection to Ex Main	EACH	2	2000	4000
638	6" Cut-in-Valve	EACH	1	1500	1500
638	8" Valve	EACH	1	1800	1800
638	10" Valve	EACH	3	2500	7500
638	8" x 6" Reducer	EACH	2	180	360
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	8000	8000
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	125	3125
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	125	5000
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	134.50	312040
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	22	2442
630	Sign Flat Sheet	SQ FT	62	15	930
630	Ground Mounted Support No. 3 Post	EACH	8	123	984
630	Removal of Ground Mounted Sign and Disposal	EACH	5	15	75
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	15	75
630	Removal of Ground Mounted Sign and Reerection	EACH	1	40	40
642	Center Line	MILE	0.57	1360	775.20

N

Resor Road

BID FORM

642	Edge Line	MILE	1	1032	1032
642	Dotted Line, 4"	LF	88	1.10	96.80
642	Channelizing Line	LF	166	1.25	207.50
642	Lane Arrow	EACH	3	80	240
642	Word on Pavement	EACH	1	105	105
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	13000	13000
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	25	23750
623	Construction Layout Staking	SUM	LUMP	10000	10000
624	Mobilization	SUM	LUMP	40000	40000
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	1000	1000
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	26	24700
	TOTAL BASE BID				1,129,719

N

Resor Road Improvements

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID 1,018,828.90

CONSIDERATION FOR MATERIAL 325,000

CONSIDERATION FOR LABOR 693,828.90

TOTAL LABOR AND MATERIAL 1,018,828.90

TOTAL AMOUNT WRITTEN IN WORDS One million Eighteen thousand Eight Hundred Twenty Eight and Ninety Cents

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

Joseph Prus — Signature
Joseph Prus — Name
President — Title
PRUS CONSTRUCTION CO. — Company
5325 Wooster Rd. — Address
Cinti, OH 45226 — City/State/Zip
321-7774 — Telephone
31-0708511 — S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
✓ Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No. 2 ✓ Yes ___ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

Resor Road

BID FORM

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	22,000.00	22,000.00
202	Fence Removed	FEET	20	7.00	140.00
202	Walk Removed	SQ YD	245	2.00	490.00
202	Pipe Removed, 24" and Under	FEET	462	7.00	3,234.00
202	Catch Basin Removed	EACH	3	200.00	600.00
202	Pavement Removed - Driveways	SQ YD	476	9.00	4,284.00
202	Special - Stone Retaining Wall Removed	EACH	3	350.00	1,050.00
203	Excavation Not Including Embankment	CU YD	3573	22.00	78,606.00
203	Embankment	CU YD	495	15.00	7,425.00
204	Proof Rolling	HOURS	3	75.00	225.00
204	Embankment	CU YD	200	12.00	2400.00
204	Subgrade Compaction	SQ YD	4025	1.50	6,037.00
204	Subgrade Compaction (Driveways)	SQ YD	305	1.50	457.50
204	Excavation of Subgrade	CU YD	300	20.00	6,000.00
204	Granular Material	CU YD	100	36.00	3,600.00
204	Geotextile Fabric	SQ YD	100	4.00	400.00
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	10.00	1,000.00
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	10.00	1,000.00
207	Erosion Control	LUMP	1	3,500.00	3,500.00
207	Tempoary Filter Fabric Fence	FEET	1300	2.50	3,250.00
207	Dandy Bags	EACH	8	95.00	760.00
207	Beaver Dams	EACH	8	125.00	1,000.00
606	Guardrail Type 5	FEET	75	27.00	2,025.00
606	Guardrail Anchor Type A	EACH	1	2,000.00	2,000.00
606	Guardrail Anchor Type E-98 Assembly	EACH	1	2,200.00	2,200.00
608	Concrete Walk	SQ FT	245	8.00	1960.00
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	450.00	900.00
609	Curb, Type 6	FEET	1020	16.00	16,320.00
659	Water	MGAL	4	5.00	20.00
659	Commercial Fertilizer	TON	2	1,000.00	2,000.00
660	Sodding	SQ YD	2332	5.50	12,826.00
690	Mailbox Support System, Single	EACH	33	150.00	4950.00
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	650.00	650.00

DRAINAGE					
Item No.	Description	Units	Est. Qty		

N

Resor Road

BID FORM

601	Rock Channel Type C with Filter Fabric	CU YD	54	65.00	3,510.00
602	Concrete Masonry	CU YD	4	1,100.00	4,400.00
603	6" Conduit, Type E	FEET	100	10.00	1,000.00
603	6" Conduit, Type F	FEET	100	10.00	1,000.00
603	12" Conduit, Type C	FEET	347	31.00	10,757.00
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	35.00	6,545.00
603	12" Conduit, Type D	FEET	525	36.00	18,900.00
603	24" Conduit, Type D	FEET	49	65.00	3,185.00
603	24" Conduit, Type C	FEET	24	90.00	2,160.00
604	Catch Basin, No. 2-2B	EACH	7	1,000.00	7,000.00
604	Catch Basin, No. 2-3	EACH	2	1,250.00	2,500.00
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	625.00	1,875.00
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	11.00	13,970.00
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	825.00	4,950.00
604	Sanitary Manhole Reconstructed to Grade	EACH	2	1,175.00	2,350.00
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	53.00	67,893.00
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	80.00	4,560.00
304	Aggregate Base	TON	1418	22.00	31,196.00
304	Aggregate Base (Driveways)	TON	46	35.00	1,610.00
254	Pavement Planing	SQ YD	5035	2.65	13,342.75
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	72.00	61,992.00
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	100.00	3,000.00
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	76.00	55,860.00
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	105.00	2,730.00
407	Tack Coat For Intermediate Course	GAL	400	2.50	1,000.00
408	Prime Coat	GAL	1600	5.50	8,800.00
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	52.00	44,096.00
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4.40	31,570.00

N

Resor Road

BID FORM

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	35,000.00	35,000.00
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1,150.00	24,150.00
638	Fire Hydrant Removed	EACH	4	375.00	1,500.00
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	4,600.00	23,000.00
638	6" Water Main Connection to Ex Main	EACH	1	2,400.00	2,400.00
638	10" Water Main Connection to Ex Main	EACH	2	2,600.00	5,200.00
638	6" Cut-in-Valve	EACH	1	1,300.00	1,300.00
638	8" Valve	EACH	1	1,100.00	1,100.00
638	10" Valve	EACH	3 MR	1,500.00	4,500.00
638	8" x 6" Reducer	EACH	2	260.00	520.00
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	15,000.00	15,000.00
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	290.00	7250.00
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	165.00	6,600.00
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	99.00	229,680.00
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	22.05	2,447.55
630	Sign Flat Sheet	SQ FT	62	14.70	911.40
630	Ground Mounted Support No. 3 Post	EACH	8	122.85	982.80
630	Removal of Ground Mounted Sign and Disposal	EACH	5	15.75	78.75
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	15.75	78.75
630	Removal of Ground Mounted Sign and Reerection	EACH	1	42.00	42.00
642	Center Line	MILE	0.57	1,400.00	798.00

N

Resor Road

BID FORM

642	Edge Line	MILE	1	1,033.00	1,033.00
642	Dotted Line, 4"	LF	88	1.05	92.40
642	Channelizing Line	LF	166	1.25	207.50
642	Lane Arrow	EACH	3	80.00	240.00
642	Word on Pavement	EACH	1	105.00	105.00
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	15,000.00	15,000.00
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	15.00	14,250.00
623	Construction Layout Staking	SUM	LUMP	7,000.00	7,000.00
624	Mobilization	SUM	LUMP	12,500.00	12,500.00
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	800.00	800.00
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	20.00	19,000.00
	TOTAL BASE BID	1,018,828.90			

N

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID 1,052,031.37

CONSIDERATION FOR MATERIAL 526,015.68

CONSIDERATION FOR LABOR 526,015.69

TOTAL LABOR AND MATERIAL 1,052,031.37

TOTAL AMOUNT WRITTEN IN WORDS ONE MILLION, FIFTY TWO THOUSAND, THIRTY ONE Dollars and THIRTY SEVEN cents.

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

Scott Rack — Signature

SCOTT RACK — Name

VICE PRES. — Title

RACK & BALLAUER EXCAVATING CO., INC. — Company

11321 PADDY'S RUN RD. (Crosby Twp.)
HAMILTON, OH 45013 — Address

City/State/Zip

513) 738-1000 — Telephone

31-1079334 — S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
X Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No. 1, 2 X Yes ___ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	12,000	12,000
202	Fence Removed	FEET	20	9.60	192.00
202	Walk Removed	SQ YD	245	15.84	3880.00
202	Pipe Removed, 24" and Under	FEET	462	10.00	4620.00
202	Catch Basin Removed	EACH	3	300.00	900.00
202	Pavement Removed - Driveways	SQ YD	476	16.00	7616.00
202	Special - Stone Retaining Wall Removed	EACH	3	750.00	2250.00
203	Excavation Not Including Embankment	CU YD	3573	15.94	56 970.00
203	Embankment	CU YD	495	6.38	3156.00
204	Proof Rolling	HOURS	3	137.00	411.00
204	Embankment	CU YD	200	700	1400.00
204	Subgrade Compaction	SQ YD	4025	1.70	6860.00
204	Subgrade Compaction (Driveways)	SQ YD	305	2.00	610.00
204	Excavation of Subgrade	CU YD	300	16.00	4800.00
204	Granular Material	CU YD	100	52.30	5230.00
204	Geotextile Fabric	SQ YD	100	4.15	415.00
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	13.00	1300.00
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	13.00	1300.00
207	Erosion Control	LUMP	1	1750.00	1750.00
207	Tempoary Filter Fabric Fence	FEET	1300	1.35	1755.00
207	Dandy Bags	EACH	8	75.00	600.00
207	Beaver Dams	EACH	8	100.00	800.00
606	Guardrail Type 5	FEET	75	25.00	1875.00
606	Guardrail Anchor Type A	EACH	1	3500.00	3500.00
606	Guardrail Anchor Type E-98 Assembly	EACH	1	3800.00	3800.00
608	Concrete Walk	SQ FT	245	6.00	1470.00
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	350.00	700.00
609	Curb, Type 6	FEET	1020	10.90	11,118.00
659	Water	MGAL	4	10.00	40.00
659	Commercial Fertilizer	TON	2	700.00	1400.00
660	Sodding	SQ YD	2332	5.00	11,660.00
690	Mailbox Support System, Single	EACH	33	165.00	5445.00
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	550.00	550.00

DRAINAGE					
Item No.	Description	Units	Est. Qty		

Resor Road

BID FORM

601	Rock Channel Type C with Filter Fabric	CU YD	54	78.00	4212.00
602	Concrete Masonry	CU YD	4	173.00	692.00
603	6" Conduit, Type E	FEET	100	9.50	950.00
603	6" Conduit, Type F	FEET	100	9.50	950.00
603	12" Conduit, Type C	FEET	347	36.00	12,492.00
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	73.00	13,651.00
603	12" Conduit, Type D	FEET	525	36.00	18900.00
603	24" Conduit, Type D	FEET	49	60.00	2940.00
603	24" Conduit, Type C	FEET	24	76.00	1824.00
604	Catch Basin, No. 2-2B	EACH	7	1800.00	12600.00
604	Catch Basin, No. 2-3	EACH	2	1900.00	3800.00
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	1200.00	3600.00
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	9.00	11430.00
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	1200.00	7200.00
604	Sanitary Manhole Reconstructed to Grade	EACH	2	3500.00	7000.00
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	51.00	65331.00
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	95.00	5415.00
304	Aggregate Base	TON	1418	19.00	26942.00
304	Aggregate Base (Driveways)	TON	46	30.00	1380.00
254	Pavement Planing	SQ YD	5035	1.50	7552.50
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	49.00	42,189.00
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	140.00	4200.00
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	68.00	49,980.00
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	115.00	2990.00
407	Tack Coat For Intermediate Course	GAL	400	2.00	800.00
408	Prime Coat	GAL	1600	4.00	6400.00
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	37.00	31,376.00
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	3.75	26,906.25

FF

N

Rcsor Road

BID FORM

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	20,380.00	20,380.00
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1350.00	28,350.00
638	Fire Hydrant Removed	EACH	4	850.00	3400.00
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	3785.00	18,925.00
638	6" Water Main Connection to Ex Main	EACH	1	5180.00	5180.00
638	10" Water Main Connection to Ex Main	EACH	2	4880.00	9760.00
638	6" Cut-in-Valve	EACH	1	2350.00	2350.00
638	8" Valve	EACH	1	1154.00	1154.00
638	10" Valve	EACH	3	1438.00	4314.00
638	8" x 6" Reducer	EACH	2	90.00	180.00
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	18150.00	18150.00
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	190.00	4750.00
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	140.00	5600.00
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	130.00	301,600.00
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	21.00	2331.00
630	Sign Flat Sheet	SQ FT	62	14.00	868.00
630	Ground Mounted Support No. 3 Post	EACH	8	117.00	936.00
630	Removal of Ground Mounted Sign and Disposal	EACH	5	15.00	75.00
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	15.00	75.00
630	Removal of Ground Mounted Sign and Reerection	EACH	1	40.00	40.00
642	Center Line	MILE	0.57	1296.00	738.72

N

Resor Road

BID FORM

642	Edge Line	MILE	1	983.00	983.00
642	Dotted Line, 4"	LF	88.	1.00	88.00
642	Channelizing Line	LF	166	1.15	190.90
642	Lane Arrow	EACH	3	75.00	225.00
642	Word on Pavement	EACH	1	100.00	100.00
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	13000.00	13000.00
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	26.00	24700.00
623	Construction Layout Staking	SUM	LUMP	12,000.00	12000.00
624	Mobilization	SUM	LUMP	12,000.00	12000.00
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	1162.00	1162.00
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	27.00	25650.00
	TOTAL BASE BID			$1,052,031.37	

N

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID $1,276,224.94

CONSIDERATION FOR MATERIAL $420,000-

CONSIDERATION FOR LABOR $856,224.94

TOTAL LABOR AND MATERIAL $1,276,224.94

TOTAL AMOUNT WRITTEN IN WORDS One Million Two hundred Seventy Six thousand-Two Hundred twenty four dollars and 94/100

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

[signature]	Signature
Richard E. Jones, Jr.	Name
President	Title
Sunesis Construction Co.	Company
2610 Crescentville Rd.	Address
West Chester, OH. 45069	City/State/Zip
513-326-6000	Telephone
31-1323837	S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
X Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No. 1, 2 X Yes _ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	36000 -	36000 -
202	Fence Removed	FEET	20	10 -	200 -
202	Walk Removed	SQ YD	245	0.50 -	122.50
202	Pipe Removed, 24" and Under	FEET	462	14 -	6468 -
202	Catch Basin Removed	EACH	3	400 -	1200 -
202	Pavement Removed - Driveways	SQ YD	476	18 -	8568 -
202	Special - Stone Retaining Wall Removed	EACH	3	150 -	450 -
203	Excavation Not Including Embankment	CU YD	3573	16 -	57168 -
203	Embankment	CU YD	495	10 -	4950 -
204	Proof Rolling	HOURS	3	200 -	600 -
204	Embankment	CU YD	200	36 -	7200 -
204	Subgrade Compaction	SQ YD	4025	3 -	12075 -
204	Subgrade Compaction (Driveways)	SQ YD	305	33 -	10065 -
204	Excavation of Subgrade	CU YD	300	16 -	4800 -
204	Granular Material	CU YD	100	32 -	3200 -
204	Geotextile Fabric	SQ YD	100	6 -	600 -
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	6 -	600 -
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	6 -	600 -
207	Erosion Control	LUMP	1	6000 -	6000 -
207	Tempoary Filter Fabric Fence	FEET	1300	2 -	2600 -
207	Dandy Bags	EACH	8	150 -	1200 -
207	Beaver Dams	EACH	8	140 -	1120 -
606	Guardrail Type 5	FEET	75	36 -	2700 -
606	Guardrail Anchor Type A	EACH	1	1100 -	1100 -
606	Guardrail Anchor Type E-98 Assembly	EACH	1	2400 -	2400
608	Concrete Walk	SQ FT	245	8 -	1960 -
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	350 -	700 -
609	Curb, Type 6	FEET	1020	15 -	15300 -
659	Water	MGAL	4	1 -	4 -
659	Commercial Fertilizer	TON	2	500 -	1000 -
660	Sodding	SQ YD	2332	6 -	13992 -
690	Mailbox Support System, Single	EACH	33	220 -	7260 -
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	500 -	500

DRAINAGE					
Item No.	Description	Units	Est. Qty		

N

601	Rock Channel Type C with Filter Fabric	CU YD	54	53-	2862-
602	Concrete Masonry	CU YD	4	1100-	4400-
603	6" Conduit, Type E	FEET	100	6-	600-
603	6" Conduit, Type F	FEET	100	6-	600-
603	12" Conduit, Type C	FEET	347	41-	14227-
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	78-	14586-
603	12" Conduit, Type D	FEET	525	36-	18900-
603	24" Conduit, Type D	FEET	49	67-	3283-
603	24" Conduit, Type C	FEET	24	79-	1896-
604	Catch Basin, No. 2-2B	EACH	7	950-	6650-
604	Catch Basin, No. 2-3	EACH	2	1300-	2600-
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	300-	900-
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	15-	19050-
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	350-	2100-
604	Sanitary Manhole Reconstructed to Grade	EACH	2	3200-	6400-
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	51-	65331-
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	104-	5928-
304	Aggregate Base	TON	1418	26.83	38044.94
304	Aggregate Base (Driveways)	TON	46	210-	9660-
254	Pavement Planing	SQ YD	5035	1.50	7552.50
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	54-	46494-
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	150-	4500-
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	75-	55125-
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	126-	3276-
407	Tack Coat For Intermediate Course	GAL	400	2-	800-
408	Prime Coat	GAL	1600	4-	6400-
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	42-	35616-
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4-	28700-

N

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	60000	60000
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1300-	27300-
638	Fire Hydrant Removed	EACH	4	350-	1400-
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	4500-	22500-
638	6" Water Main Connection to Ex Main	EACH	1	2100-	2100-
638	10" Water Main Connection to Ex Main	EACH	2	3100-	6200-
638	6" Cut-in-Valve	EACH	1	3400-	3400-
638	8" Valve	EACH	1	1000-	1000-
638	10" Valve	EACH	3	1600-	4800-
638	8" x 6" Reducer	EACH	2	200-	400-
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	37000-	37000-
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	107-	2675-
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	127-	5080-
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	132-	306240-
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	23-	2553-
630	Sign Flat Sheet	SQ FT	62	15-	930-
630	Ground Mounted Support No. 3 Post	EACH	8	128-	1024-
630	Removal of Ground Mounted Sign and Disposal	EACH	5	16-	80-
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	16-	80-
630	Removal of Ground Mounted Sign and Reerection	EACH	1	44-	44-
642	Center Line	MILE	0.57	1400-	798-

N

642	Edge Line	MILE	1	1100-	1100-
642	Dotted Line, 4"	LF	88	1-	88-
642	Channelizing Line	LF	166	1.50	249-
642	Lane Arrow	EACH	3	80-	240-
642	Word on Pavement	EACH	1	110-	110-
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	13000-	13000-
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	54-	51300-
623	Construction Layout Staking	SUM	LUMP	12000-	12000-
624	Mobilization	SUM	LUMP	40000-	40000-
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	1100-	1100
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	55-	52250-
	TOTAL BASE BID			$ 1,276,224.94	

N

THE CITY OF FAIRFIELD RESERVES THE RIGHT TO DELETE OR CHANGE THE QUANTITY OF ANY ITEM LISTED ABOVE.

TOTAL BASE BID 1,043,998.35

CONSIDERATION FOR MATERIAL 500,000.00

CONSIDERATION FOR LABOR 543,998.35

TOTAL LABOR AND MATERIAL 1,043,998.35

TOTAL AMOUNT WRITTEN IN WORDS One million, forty three thousand, nine hundred ninety eight and 35/100 dollars

The undersigned, having full knowledge of the site, plans and specifications for the above improvement and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project according to the plans, specifications and completion date, and to accept the unit prices specified on the bid form for each item as full compensation for the work in this proposal.

Daniel R Rapier — Signature

Daniel Rapier — Name

Pres/C.E.O. — Title

REI Construction — Company

4845 Augspurger Road — Address

Hamilton, Ohio 45011 — City/State/Zip

513-868-9087 — Telephone

31-1095258 — S.S. # of Company Owner/or Federal I.D. #

Note: Please indicate type of bid security:
x Bid Bond ___ Certified Check ___ Cashier's Check
Addenda Received: No.___ x Yes _ No
Work will start within fifteen (15) days after Notice to Proceed.

Work will be completed within 150 calendar days after Notice to Proceed.
Road Closure will be limited to 60 calendar days.

Liquidated damages, as pursuant to Section E 15.3 of these specifications and Section 108.07 of the ODOT Construction and Materials Specifications, will be $1000.00 per day.

Resor Road

BID FORM

ROADWAY					
Item No.	Description	Units	Total Est. Qty	Unit Price	Total Price
201	Clearing and Grubbing	SUM	LUMP	17000.00	17000.00
202	Fence Removed	FEET	20	13.25	265.00
202	Walk Removed	SQ YD	245	3.60	882.00
202	Pipe Removed, 24" and Under	FEET	462	12.25	5659.50
202	Catch Basin Removed	EACH	3	250.00	750.00
202	Pavement Removed - Driveways	SQ YD	476	5.30	2522.80
202	Special - Stone Retaining Wall Removed	EACH	3	420.00	1260.00
203	Excavation Not Including Embankment	CU YD	3573	15.00	53595.00
203	Embankment	CU YD	495	11.00	5445.00
204	Proof Rolling	HOURS	3	110.00	330.00
204	Embankment	CU YD	200	45.00	9000.00
204	Subgrade Compaction	SQ YD	4025	1.85	7446.25
204	Subgrade Compaction (Driveways)	SQ YD	305	2.25	686.25
204	Excavation of Subgrade	CU YD	300	20.00	6000.00
204	Granular Material	CU YD	100	40.00	4000.00
204	Geotextile Fabric	SQ YD	100	.60	60.00
204	Filter Fabric with Tensar Geogrid (TX-7) or Approved Equal	SQ YD	100	5.50	550.00
SPEC	BX 1300 Tensar Reinforcement or approved equal	SQ YD	100	4.90	490.00
207	Erosion Control	LUMP	1	4000.00	4000.00
207	Tempoary Filter Fabric Fence	FEET	1300	3.00	3900.00
207	Dandy Bags	EACH	8	45.00	360.00
207	Beaver Dams	EACH	8	65.00	520.00
606	Guardrail Type 5	FEET	75	31.00	2325.00
606	Guardrail Anchor Type A	EACH	1	925.00	925.00
606	Guardrail Anchor Type E-98 Assembly	EACH	1	2250.00	2250.00
608	Concrete Walk	SQ FT	245	6.00	1470.00
608	Curb Ramp With Truncated Domes (As Per Plan)	EACH	2	325.00	650.00
609	Curb, Type 6	FEET	1020	15.00	15300.00
659	Water	MGAL	4	110.00	440.00
659	Commercial Fertilizer	TON	2	550.00	1100.00
660	Sodding	SQ YD	2332	5.00	11660.00
690	Mailbox Support System, Single	EACH	33	180.00	5940.00
SPEC	Mailbox Relocated, 1900 Resor Road	EACH	1	225.00	225.00

DRAINAGE					
Item No.	Description	Units	Est. Qty		

N

Resor Road BID FORM

601	Rock Channel Type C with Filter Fabric	CU YD	54	100.00	5400.00
602	Concrete Masonry	CU YD	4	475.00	1900.00
603	6" Conduit, Type E	FEET	100	6.00	600.00
603	6" Conduit, Type F	FEET	100	6.00	600.00
603	12" Conduit, Type C	FEET	347	28.50	9889.50
603	12" Conduit, Type B, 706.02 reinforced concrete pipe	FEET	187	80.00	14960.00
603	12" Conduit, Type D	FEET	525	40.00	21000.00
603	24" Conduit, Type D	FEET	49	63.00	3087.00
603	24" Conduit, Type C	FEET	24	53.00	1272.00
604	Catch Basin, No. 2-2B	EACH	7	850.00	5950.00
604	Catch Basin, No. 2-3	EACH	2	1525.00	3050.00
604	Catch Basin/Manhole Adjusted to Grade	EACH	3	425.00	1275.00
605	6" Base Pipe Underdrain with Fabric Wrap	FEET	1270	6.50	8255.00
SANITARY					
604	Sanitary Manhole Adjusted to Grade, As Per Plan	EACH	6	650.00	3900.00
604	Sanitary Manhole Reconstructed to Grade	EACH	2	1450.00	2900.00
PAVEMENT					
Item No.	Description	Units	Est. Qty		
301	Asphalt Concrete Base, PG 64-22	TON	1281	54.00	69174.00
301	Asphalt Concrete Base, PG 64-22 (Driveways)	TON	57	103.00	5871.00
304	Aggregate Base	TON	1418	23.00	32614.00
304	Aggregate Base (Driveways)	TON	46	40.00	1840.00
254	Pavement Planing	SQ YD	5035	1.60	8056.00
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28	TON	861	54.00	46494.00
448	Asphalt Concrete Intermediate Course, Type 2, PG 64-28 (Driveways)	TON	30	152.00	4560.00
448	Asphalt Concrete Surface Course, Type 1H, PG 70-22	TON	735	75.00	55125.00
448	Asphalt Concrete Surface Course, Type 1, PG 64-28 (Driveways)	TON	26	125.00	3250.00
407	Tack Coat For Intermediate Course	GAL	400	2.20	880.00
408	Prime Coat	GAL	1600	4.40	7040.00
452	8" Non-Reinforced Concrete Pavement (Driveways)	SQ YD	848	45.00	38160.00
SPEC	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	SQ YD	7175	4.25	30493.75

Resor Road

BID FORM

MAINTENANCE OF TRAFFIC					
Item No.	Description	Units	Est. Qty		
614	Maintaining Traffic	SUM	LUMP	35000.00	35000.00
WATER WORK					
Item No.	Description	Units	Est. Qty		
604	Reset Ex Water Meter and Reconnect Ex Water Service	EACH	21	1300.00	27300.00
638	Fire Hydrant Removed	EACH	4	650.00	2600.00
638	Fire Hydrant (Including 6" Water Main Extension,Tee, and Valve)	EACH	5	4100.00	20500.00
638	6" Water Main Connection to Ex Main	EACH	1	2000.00	2000.00
638	10" Water Main Connection to Ex Main	EACH	2	2500.00	5000.00
638	6" Cut-in-Valve	EACH	1	1500.00	1500.00
638	8" Valve	EACH	1	1250.00	1250.00
638	10" Valve	EACH	3	1850.00	5550.00
638	8" x 6" Reducer	EACH	2	100.00	200.00
638	Jack and Bore 10" DI Water Main including Casing Pipe	LUMP	1	12000.00	12000.00
638	6" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	25	126.00	3150.00
	Per City of Fairfield Requirements				
638	8" Water Main DI CL 53 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	40	126.00	5040.00
	Per City of Fairfield Requirements				
638	10" Water Main DI CL 55 w/ Polywrap Includes all Bends, Tees, Fittings etc	FT	2320	116.00	269120.00
	Per City of Fairfield Requirements				
TRAFFIC CONTROL					
Item No.	Description	Units	Est. Qty		
621	RPM	EACH	111	23.00	2553.00
630	Sign Flat Sheet	SQ FT	62	15.00	930.00
630	Ground Mounted Support No. 3 Post	EACH	8	125.00	1000.00
630	Removal of Ground Mounted Sign and Disposal	EACH	5	15.00	75.00
630	Removal of Ground Mounted Post Support and Disposal	EACH	5	15.00	75.00
630	Removal of Ground Mounted Sign and Reerection	EACH	1	50.00	50.00
642	Center Line	MILE	0.57	1400.00	798.00

N

642	Edge Line	MILE	1	1050.00	1050.00
642	Dotted Line, 4"	LF	88	1.10	96.80
642	Channelizing Line	LF	166	1.25	207.50
642	Lane Arrow	EACH	3	80.00	240.00
642	Word on Pavement	EACH	1	110.00	110.00
SPEC	Special - Warning Light Pole to Be Removed and Reset Including Foundation	LUMP	1	12500.00	12500.00
MISCELLANEOUS ITEMS					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Allenblock Wall or Approved Equal	SF	950	32.00	30400.00
623	Construction Layout Staking	SUM	LUMP	12000.00	12000.00
624	Mobilization	SUM	LUMP	3000.00	3000.00
SPEC	Remove and Reset Existing Handrail (1923 Resor)	EACH	1	850.00	850.00
ALTERNATIVE #1					
Item No.	Description	Units	Est. Qty		
610	Cellular Retaining Wall, Keystone Wall or Approved Equal	SF	950	35.00	33250.00
	TOTAL BASE BID				$1,043,998.35

N